

Clearing Wreckage To Inject U4 SFP Cooling Water





**Debris Was Blocking
Pumper Access to SFP**




**Debris Cleared For Pumper
By Manual Tank-Bulldozer**

Established Pool Recirculation Cooling


Progress status of cooling (Spent Fuel Pool) (Description)

Issues	Countermeasures	Implementation status	Photos and figures
1. Cooling (2) Spent Fuel Pools Unit 1	Countermeasure[22] Continuation of water injection by "Giraffe", etc	-Reliability improvement: enhanced durability of hoses -Measures to reduce radiation dose: switch to remote-controlled operation (arm, water injection operation)	<div data-bbox="956 335 1574 364" data-label="Caption"> <p>Image of remote control operation of concrete pumping vehicle</p> </div>  <div data-bbox="1362 449 1787 478" data-label="Caption"> <p>Installation of camera at the top of the arm</p> </div> 
	Countermeasure[24] Restoration of normal cooling system	-Radiation measurement by ycamera and robot(from April 30 to May 6) -Radiation reduction by flushing and shielding facility(from May 11 to May 15)	<div data-bbox="927 871 1371 1270" data-label="Diagram"> </div> <div data-bbox="946 1278 1410 1320" data-label="Caption"> <p>Overview of SFP cooling function</p> </div> <div data-bbox="1381 863 1806 1335" data-label="Image"> <div data-bbox="1391 1106 1555 1135" data-label="Caption"> <p>cooling tower</p> </div> <div data-bbox="1487 1292 1787 1328" data-label="Caption"> <p>plate type heat exchanger</p> </div> </div>
	Countermeasure[25.2] Install heat exchanger	-Manufacturing heat exchanger	

Release Periods Based On Site Gamma Levels




Establishing Core Recirculation Cooling In Early July




Recirc Core Cooling

System outline of water reuse as reactor coolant by processing accumulated water




Countermeasure to Seal the Damaged Location in the PCV of the Unit 2



Current Primary Containment Integrity

Oxygen-Hydrogen Risk




- Hydrogen & Steam Atmosphere
Currently In Primary Containments

- As System Cools May Draw Air with
Oxygen Back Into the Containment
and Could Become Explosive

- Currently Injecting Inert nitrogen to
Prevent Oxygen In-leakage, however
Unit 3 has significant containment
leakage

Current Primary Containment Integrity

Seismic Risk




- Primary Containments are Partially Flooded with Core Feed Water Outflow Well Beyond Design Basis Levels
- Earthquake Aftershocks Add Increased Dynamic Stress to Higher than Design Static Stress
- Reactor Building Structure Has Likely Been Degraded by Explosions and initial Earthquake To an Unknown Degree
- Containment Integrity Margins being Evaluated

Current Unit 4 Reactor Building

Structural Integrity Seismic Risk





- Explosions Have Weakened RB Structure
- A Large Earthquake Aftershock May Cause Building Failure
- Keeping Pool Water Level at a Minimum to reduce Loads



- Adding Steel & Concrete under Pool

• High Gamma Field Causing Delays⁹

Gather Data Inside Reactor Buildings



**Adapted Military Drones With
Thermal & Radiation Capabilities**

**Inside Reactor Buildings
~1-100R/Hr & U2 High Vapor**

Working Conditions are Challenging

Restoring Power In High Radiation & Contaminated Areas



Control Room Power Restoration



Before Power Restored



After Power Restored

Working In Contaminated Buildings



**Entering Waste
Processing Building**



**Worker Showing TB Basement
Floor Water Level**

Reactor Building Air Filtration

Access to Calibrate Reactor Water Level Instrumentation



U2 Reactor Building Conditions




Robots First



Personnel Second

Ground RB Floor



Water 4M deep in Basement


U3 Reactor Building Conditions



Robotic Vacuum Cleaner



50-20mm Steel Plate Floor Shielding




Reducing 5-18R/hr Gamma Fields
 For N2 Containment Injection

Airborne Mitigation



Dust Suppression Resin Application



**Unit 1 Fabric Enclosure
55M High & 47M X 42M**

Unit 1 Canopy Design/Construction Process



Laser Measure Existing Building



Laser Image New Enclosure



Construction Sequence Planing



New Fast Const Concepts



Mockup Const Training

Minimizing Building Rain In Leakage

Unit 1 Turbine Building Roof Patch To Reduce Radioactive Water Overflow




Current Rainy Season: Typhoon Ma On with 4" last week

Contaminated Water Accumulating

- **Feed & Bleed Core Cooling Flushed Large Amounts of Highly Radioactive Water into Building Basements**
- **Approximately 30 Million Gallons Now**
- **Approximately 25 Million Curies**
- **Increasing at ~100,000 gallons per day**
- **Rainy Season Adding More**

Effluent Release Flow Paths

Reactor Building-Turbine Building-Intake -Sea



Contaminated Water Containment Overflow from U2 Reactor Bldg to Turbine Bldg to Intake Structure Wall Crack to Sea

27,000 Ci Cs-137 Released this Path 4/1-6

-Reference Chernobyl was 2MCi Cs-137 released



**Non-Safety Grade
intake Structure**



**Radioactive Water
Leak 11-04-02**



Leak Reduced 11-04-04


**Leak Sealed 11-04-06
Sodium Silicate Injection**

Contaminated Water Containment

How the Intake Wall Crack Leak was Stopped



Cable Chase Path



Leak Sealed 11-04-06

Sodium Silicate Injection


Other Similar Leakage Paths To Seal

Sealing Other Leakage Paths to Sea



Concreting One of ~37 Cable & Pipe Chase Paths

Mitigate Basement Leakage Into Groundwater Paths To Sea




Planning Underground Barrier Walls to Bed Rock

Water Retention Tank Farms

Underground Tanks Under Construction



Accident Water Management



20-50 Million Gallons Of Highly Radioactive Water To Be Transferred To Onsite Tankage

Water Release Mitigation

Contain/Retard Intake Structure Cs/Sr Contamination



**Sluice Gate to Minimize Outflow
To Ocean**



Zeolite Bags To Adsorb Cs/Sr

Water Release Mitigation

Silt Fence to Retard Cs/Sr Release to Sea



Process Intake Canal Water Through Zeolite Beds to Remove Released Cesium



US Fresh Water Barge On Site-April



Japanese ship hauling US Navy water barge



Japanese Tow Operators

New Water Barge On Site-June




2.5 Million Gallon Capacity Barge

L. Barrett Consulting LLC

Accident Water Treatment Plans

~30 Million Gallons in Basements

Image of coagulation precipitation




Treatment equipment

1200T/day (330Kgal/day or 200gpm) Rate Goal with 1E3 DF Startup Late June

Water Recirculation Processing Plan

Four Stage System

1. Oil Removal: Toshiba
2. Cesium Removal: Kurion
3. Fission Products Removal: AREVA
4. Salt Removal: Hitachi



* oil separators, radioactive material treatment instruments... Installed within the Process Main Building,

Cesium absorption Instruments... Installed within the Incineration Workshop Building

L. Barrett Consulting LLC

Oil Removal



Separator Unit



Separator Internals

Cesium Removal Stage




Individual Zeolite Beds



Shielded Skids



Fission Product Precipitation Stage




Chemical Injection Tanks




Installed Co-Precipitation Unit

Process System Locations



Water Tank & Systems Locations



Water Processing Difficulties With First Kurion/AREVA System



Many Systems Leaks & Issues

~60% Capacity

High Rad Sludge Management Challenges Will Emerge

New Water Processing System

Simplified Active Water Retrieve and Recovery System (SARRY)




Toshiba Lead

2 Lines of 8 Larger (24Ton) Zeolite/Silicate Filter Beds to replace/augment Initial Kurion/AREVA System

Planned August Operation

Site Needs Extensive Decon



Debris Hotspots

100R/hr



Decontamination-Cleanup

High Radiation Field Work with Remotely Operated Equipment



**Remote Equipment
Operator**



**Remotely Operated
Construction Equipment
Reducing Gamma Field and
Debris Removal**

Decontamination Cleanup Solids



**Remote Debris Removal
-90R/Hr Concrete Piece**



**Remote Debris Transporter
With Solid Waste Container**

Onsite Solid Storage Area



~300+ 4M3 Containers to June

Solid Waste Handling Equipment



Shielded Fork Lift



Remote Controlled Equipment

On Site Personnel Facilities



Shielded Work Areas



Change House



Rest Areas

Off Site Personnel Facilities



Temporary Dani Gym Dormitory




New Hirono Dormitory

Personnel Exposures

- **~4,000 Onsite Personnel**
- **Most are $< 100 \text{ mSv}$ (10R)**
- **~100 are $>100\text{mSv}$ (10R) $< 250\text{mSv}$ (25R)**
- **~6 are ~ 500-600mSv (50 to 60R)**
 - **Over Exposures**
 - **Internal Ingestions Issue**
 - **More Likely**

Offsite impacts



School Playground Dose Remediation

Offsite Cs/Sr Contamination

Offsite: Very Low Level Tsunami Debris

Millions of tons- Incinerate w Ash Disposal <8K Cs Bq/kg



Human Feelings & Reactions



TEPCO ROADMAP SEQUENCE 06-17

Current Status of Roadmap (issues/targets/major countermeasures) as of June 17

Appendix 1

Red colored: newly added to the previous version. Blue colored: modified from the previous version

Issues	As of April 17	Step 1 (around 3 months) Current status (as of June 17)	Step 2 (around 3 to 6 months after achieving Step 1)	Mid-term issues
I. Cooling	(1) Reactor	<p>Fresh water Injection</p> <p>Cooling by minimum injection rate (injection cooling)</p> <p>Consideration and preparation of reuse of accumulated water</p> <p>Nitrogen gas injection</p> <p>Consideration and implementation of sealing measure at leaking points of PCV</p> <p>Improvement of work environment</p>	<p>Circulating Injection Cooling (start)</p> <p>Stable cooling</p> <p>Circulating Injection Cooling (continued)</p> <p>PCV flooding</p> <p>Securing heat exchange function</p> <p>Cold shutdown condition</p>	<p>Protection against corrosion cracking of structural materials</p> <p>*to be partially implemented ahead of schedule</p>
	(2) Spent Fuel Pool	<p>Fresh water Injection</p> <p>Reliability improvement in injection operation /remote-control operation *ahead of schedule</p> <p>Circulation cooling system (installation of heat exchanger) *partially ahead of schedule</p>	<p>Stable cooling</p> <p>Remote-controlled injection operation</p> <p>Consideration / installation of heat exchanging function</p> <p>More stable cooling</p>	<p>Removal of fuels</p>
II. Mitigation	(3) Accumulated Water	<p>Transferring water with high radiation level</p> <p>Storing water with low radiation level</p> <p>Installation of storage / processing facilities</p> <p>Installation of storage facilities / decontamination processing</p>	<p>Secure storage place</p> <p>Expansion of storage / processing facilities</p> <p>Decontamination / Desalt processing (reuse), etc</p> <p>Storage / management of sludge waste etc.</p> <p>Mitigation of contamination in the ocean</p> <p>Reduction of total amount of contaminated water</p>	<p>Installation of full-fledged water processing facilities</p> <p>Completion of processing of accumulated water in buildings</p> <p>Processing of sludge waste etc.</p> <p>Mitigation of contamination in the ocean (continued)</p>
	(4) Ground water	<p>Mitigation of contamination of groundwater</p>	<p>Mitigate ocean contamination (continued)</p> <p>(Sub-drainage management with expansion of storage / processing facilities)</p> <p>Consideration of shielding wall of groundwater</p>	<p>Solidification of contaminated soil, etc</p> <p>Establishment of shielding wall of groundwater</p>
	(5) Atmosphere / Soil	<p>Dispersion of inhibitor</p> <p>Removal of debris</p>	<p>Mitigate scattering</p> <p>Installing reactor building cover (with ventilation system)</p> <p>Consideration of reactor building container</p>	<p>Installation of reactor building container</p>
			<p>Mitigate ocean contamination (continued)</p> <p>Mitigate scattering (continued)</p>	

Current & Emerging Issues

- **Maintain Sustainable Closed Cooling**
- **After Shock Structural Integrity**
- **Containment Degradation**
- **High Rad Water Containment**
 - ~30+ Million Gallons
- **Highly Rad Water Processing Sludge**
 - ~1,000R/hr range
 - 20-100 Mega Curie Amounts (TMI~1MCi)
 - Impact Site Recovery
- **Building Containment/Filtration**
- **Offsite Remediation**
- **Management Restructure**
- **Regulatory Restructure**
- **Finance?**

Internal Accident Recovery Phases

1. Energy Heat Rejection Control
 1. Much Improved with Closed Residual Heat Removal
- Gas Release Control/Mitigation
 1. Containments
 2. Filtration
1. Liquid Release Control/Mitigation
 1. Control Highly Radioactive Water in Basements
 2. Initially Contain in Tanks
 3. Create Effective Purification Systems
2. Solids/Contamination Control Materials Management
 1. Contain/package
 2. Store/transport
 3. Dispose

External Phases Of Accident

- **Plant Accident Recovery Period**
 - Impossible Information Demands
 - Stabilize/Remediate/Recover/Protect
 - Hours-Days-Weeks-Months-Years-Decades
- **Environmental Impact Period**
 - Public Perception/Impacts/Remediation (Offsite)
 - Weeks-Months-Years
- **Societal/Institutional Reactions Period**
 - Cultural
 - Political
 - Policy
 - Financial
 - Management

Personal Fukushima Observations

- **Not a Public Health Catastrophe**
 - Radiological Impacts Inconsequential Compared to Earthquake/Tsunami Impacts
- **Is An Industrial Plant Catastrophe Caused By A Natural Disaster**
 - The Tsunami was the Main Safety Issue
 - Three Melted Cores & Severely Damaged & Contaminated Buildings
 - Units 1-4 Complete Loss, Units 5 & 6 Technically Recoverable
 - Cleanup Long & Expensive, but Technically Achievable (Much Larger than TMI)
- **Energy Dissipation is Getting Better, but Safety Challenges**
 - Aftershock Safety
 - System & Containment Degradation
 - Building Access Difficult
- **Environmental Release Mitigation is a Growing Challenge**
 - Water & Airborne Radioactive Effluents
 - Onsite & Offsite Environmental Impact Mitigation
- **Multiple Management, Social, Political & Economic Issues Ahead**
 - E.G. Waste & Spent Fuel Disposition Pathways
- **Lessons Learned Ahead**

Personal U.S. Nuclear Safety Observations

- **Current Reactors Have Adequate Safety Margins**
 - U.S. Tsunami Risks are Limited To Only A Few U.S. Sites
- **Past Risk Informed Severe Accident Improvements Have Already Addressed Many Fukushima Issues**
 - Station Blackout & 911 Improvements
- **Systematic, Methodical, & Risk Informed Fukushima Lessons Learned Evaluations Are Appropriate**
 - Industry
 - NRC
 - Resist “Quick Fix” Emotional Reactions
 - Continuous Improvement Culture Will Further Strengthen U.S. Capabilities
- **Lessons Learned From TMI Lessons Learned**
 - TMI Lessons Learned Greatly Improved US Nuclear Safety and Productivity
 - Most Painful Lessons are the Most Teachable
 - Fukushima Lessons Should Improve Safety and Advance Global & U.S. Nuclear Energy As Three Mile Island Lessons Learned Did Thirty Years Ago.

Lake H. Barrett

Lake@Lbarrett.com

Lake Barrett is a part time independent consultant in the energy field. He has worked in the nuclear energy and nuclear materials management areas for over 4 decades, most recently as the former head of the US Department of Energy's Office of Civilian Nuclear Waste Management which is responsible for implementing the United States' programs for spent nuclear fuel and high-level radioactive waste, as mandated by the Nuclear Waste Policy Act. In that capacity, he led the complex scientific Yucca Mountain Geologic Repository program through the statutory site selection process culminating with the Presidential site designation and following successful House and Senate votes.

He also served at U. S. Nuclear Regulatory Commission, where he was directly involved with the early response to the Three Mile Island reactor accident and became the Site Director, responsible for regulatory programs during the stabilization, recovery, and cleanup of the damaged reactor. He also has had extensive managerial and engineering experiences in DOE's Defence Programs and private industry at both Bechtel Power Corporation, with commercial nuclear power plants, and Electric Boat Division of General Dynamics with nuclear reactor and submarine systems design, operation, and decommissioning.